Press tools designed, built and run in Walsall. One team, tool to PPAP.

Genex UK designs and builds progressive, compound and single-stage press tools, then runs medium to high volume pressings, welded assemblies and finished parts on the same site. Family-owned since 2001, with roots in the 1980s, supplying automotive Tier 1s and industrial customers in the UK, Europe and North America.

QUALITY	APPROVAL	TOOLING	GAUGE	VOLUMES / YR
ISO 9001	**PPAP L3**	**12–17 wks**	**0.5–3.0 mm**	**1–250k+**

Press tooling & pressings

Tool types	Progressive · compound · single-stage
Material thickness	0.5 – 3.0 mm
Materials	DC01–DC04, HC340LA–HC420LA, S355, 304/316, 5xxx/6xxx Al
Annual volumes	5,000 – 250,000+ per part
Presses	Mechanical & hydraulic · list on request
In-die / secondary	Nut, stud & peg insertion · projection weld
Checking fixtures	Designed with the tool, included in tooling cost

Supporting processes

Laser cutting	Fibre laser, up to 25 mm
Folding	CNC press brakes
Machining	Turning · milling · grinding
Welding	Projection · spot · MIG · TIG
Assembly	Sub-assemblies, packed to line-side spec
Finishing (managed)	E-coat · zinc / zinc-nickel · powder coat
Prototypes	Laser-cut and folded, no tooling

Industries

Automotive & EV

Console, chassis, heater and pump brackets for Tier 1 interior and EV-systems suppliers. Worked to OEM material and coating specs.

Vehicle start-ups

Laser-cut prototypes first, production tooling quoted as a separate decision once the design is frozen.

Industrial

Construction, medical and consumer pressings where unit cost and consistency decide the programme.

GENEX UK LTD
Fryers Road, Leamore Industrial Estate, Walsall
WS2 7NA, United Kingdom

SALES
+44 (0)1922 710050
sales@genexuk.co.uk

WEB
genexuk.co.uk

COMPANY
Reg. 04157489
VAT GB 775 9414 84

From RFQ to PPAP

01 **RFQ review & DFM**: an engineer replies within one working day

02 **Quotation**: piece price, tooling broken down tool by tool, lead times and assumptions

03 **Tool design approval**: strip layout and design signed off with you

04 **Build, try-out & sampling**: first-off parts with dimensional report

05 **PPAP / PSW**: Level 3 as standard, about 4 weeks after tooling

06 **Serial production**: to your call-offs, packed to your spec

PPAP Level 3 contents

PSW & design records	Included
Process flow, PFMEA, control plan	Included
Full dimensional layout	Included
Material & coating results	Mill certs + coating reports
Initial process studies	Cpk / Ppk on special characteristics
MSA / gauge R&R	Included
Checking fixture	In tooling cost
Packaging approval	To customer spec

In production

- First-off, patrol and last-off inspection to the control plan
- Tool maintenance on stroke count, with a logged history for each tool
- Lot traceability from coil to delivery note
- 8D corrective action with named owner and dated containment
- Customer tooling stored and maintained while in production

Commercial terms

Tooling payments	30% order · 30% design · 30% tool complete · 10% PPAP
Tool ownership	Customer, once paid
Incoterms	EXW standard · FCA · DAP · DDP on request
Currencies	GBP · EUR · USD
Tool transfers	Assessed, refurbished, re-validated
Tool export	Built & proven in Walsall, shipped to your press

What to send with an RFQ

- 3D model (STEP / IGES) and 2D drawing with tolerances
- Material spec and thickness, plus accepted equivalents
- Annual volume and programme life
- Finish / coating specification and secondary operations
- PPAP level and packaging requirements
- Delivery location and Incoterms

Send us a drawing. An engineer replies within one working day.

genexuk.co.uk/rfq · sales@genexuk.co.uk · +44 (0)1922 710050

GENEX UK LTD
Fryers Road, Leamore Industrial Estate, Walsall WS2 7NA, United Kingdom

SALES
+44 (0)1922 710050
sales@genexuk.co.uk

CERTIFICATES
ISO 9001:2015 certificate on request

ISSUE
v1 · October 2026